

PROVIDE SIDEWALL FLASHING OR RETURN TPO ROOFING UP TO TERMINATION BAR AS INDICATED - TARGET APPROX. 8" HIGH FLASHING

KEEP EXTG. POSTS AND RAILINGS AS SUITABLE, REPLACE ROT AS NEEDED.

PROPOSED ASSEMBLY AND STRUCTURE, FOR DISCUSSION:
PLY SHEATHING OVER LVL DECKING ON FLAT. NEW LEDGER AT WALL.
NEW CRANKED BEAM AT POSTS.
COULD BE CUT FROM DEEPER BEAM, OR CONNECTED, USING CANTILEVER OF SLOPED PORTION.

DEMOLISH EXISTING STAIR ROOF (ROTTED)
REPLACE WITH NEW, NOTE CHANGES IN SLOPE DIRECTION
TRIM EXISTING POSTS, MAINTAIN HEIGHT AT TOP OF STAIR.
PROVIDE NEW BEAM AND LEDGER, TRIM W/ 1X WOOD.
USE LIFESPAN/P5 TRIM TYP.
TPO MEMBRANE ROOFING OVER UNDERLAYMENT AND PLYWOOD SHEATHING ON LVL FRAMING ON FLAT.

ROOF SLOPES :
N-S: SLOPE AWAY FROM BUILDING 1/2" - 1" .
E-W: NO SLOPE OVER UPPER LANDING, ~2"
SLOPE E-W FOR REMAINDER

2 South Elevation Proposed
3/16" = 1'-0"

REVISED SIDEWALL FLASHING

VERMONT INTEGRATED ARCHITECTURE, PC

DATE ISSUED:
04/14/2026

Drawn: NW
Checked: AN
REVISIONS:

BERP: LAWRENCE MEMORIAL LIBRARY

ROOF AT BASEMENT STAIR

SK-01